BRUHATH BANGALORE MAHANAGARA PALIKE,

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Modified Schedule - B

BBMP/2018-19/OW/WORK_INDENT34724

NAME OF WORK:Construction of Public Sitting flatform of Karekallu, Sidedahalli, Manjunatha Nagara , BTS Extn. Aralikatty & Mutturaya Katty 12th cross in Bagalagunte Ward No.14

Sl. No	Description of work	Unit	Qty	Approved rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications	Cum	23.86	6000.00	Rupees Six Thousand Only
2	Above 125%	Cum	19.00	5325.41	Rupees Five Thousand Three Hundred Twenty Five and Forty One Paise Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification	Cum	163.80	9000.0	Rupees Nine Thousand Only
4	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specificationsMORTH Specification No.1600 & 2200	Tonne	9.64	90000.00	Rupees Ninety Thousand Only
5	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	166.43	150.00	Rupees One Hundred Fifty Only

Jayaram K.

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,

6	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications.	Cum	30.06	921.74	Rupees Nine Hundred Twenty One and Seventy Four Paise Only
7	SRB 2-2 : Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications. in hard soil.(6/2.4)	Cum	136.37	460.36	Rupees Four Hundred Sixty and Thirty Five Paise Only
8	KSRB15-5 : Providing rough cement plastering 15mm thick in single coat with cement mortar to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.cement mortar 1:4	Sqm	152.94	210.19	Rupees Two Hundred Ten and Eighteen Paise Only
9	Providing and fixing granite flooring in combination of 19mm thick (Avg) gang saw water cut LAKARED granite with 86% and with 14% of 19mm thicl (avg) Black granite in CM 1:4 proportion with a coat of rough plastering using CM 1:4, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, grooves in joints including cost of curing etc., complete including cost and conveyance of all materials, mortar, labour for all items of work, HOM etc., complete as per specification	Sqm	135.78	3561.89	Rupees Three Thousand Five Hundred Sixty One and Eighty Nine Paise Only
10	Providing and fixing of wall cladding using 20mm thick gang saw water cut Shiva gold granite, grey granite in CM 1:3 proportion cut to required shape, pattern with paper joints, finished with cement mortal using white cement and colour pigments to match the colour of slab making through jointing with sealant, making holes 25mmx12mm grooves in joints including cost of all materials, mortar, labour, curing etc., complete as per specification.	Sqm	137.48	3631.61	Rupees Three Thousand Six Hundred Thirty One and Sixty One Paise Only

Jayaram.K.

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division.

	Providing half nosing for 40mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM etc., complete as per specification	Rmt	112.92	369.11	Rupees Three Hundred Sixty Nine and Ten Paise Only
12	KSRB 24-9 : Cleaning and washing of stone masonry wall surface with nitric acid including cost of materials, labour, complete as per specifications. Specification No.KBS	Sqm	102.41	5.13	Rupees Five and Twelve Paise Only
13	Providing & fixing Precast RCC slab of 100mm thick for drain in cement concrete 1:1:5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortar including from work lift charges, curing and concrete finished surface on both side etc complete as per specification with all lead and lift and as per the directions of the Engineer incharge	Sqm	65.34	1526.66	Rupees One Thousand Five Hundred Twenty Six and Sixty Five Paise Only
14	KSRB 2.5 : Earthwork excavation in all soil deposits and filling sides of foundation upto plinth in layers not exceeding 20cms. in depth, compacting each deposited layer by ramming after watering with all lead and lift including cost of all labour complete as per specifications. specification. No. KBS	Cum	41.82	413.20	Rupees Four Hundred Thirteen and Nineteen Paise Only
15	Providing half nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM etc., complete as per specification	Rmt	143.38	184.55	Rupees One Hundred Eighty Four and Fifty Five Paise Only
16	KSRB 5-14: Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 with solid concrete blocks of size 400x150x200mm	Sqm	33.20	947.38	Rupees Nine Hundred Forty Seven and Thirty Seven Paise Only
17	KSRB 5-15: Providing and constructing non load bearing wall with solid concrete blocks of size 400x100x200mm having a block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications	Sqm	17.19	831.52	Rupees Eight Hundred Thirty One and Fifty One Paise Only

Signature of the Contractor,

Executive Engineer
Dasarahalli Division

18	KSRB 8.1 : Providing and fixing in position stone slab roofing 10 to 12 cms thick laid to line and level over wooden rafters or R.C.C. battens, pointing exposed joints with cement mortar 1:4 including cost of materials, labour, curing complete as per specifications. (wooden rafters and R.C.C. battens to be paid seperately) Specification No. KBS	Sqm	14.60	1187.30	Rupees O Thousand O Hundred Eigh Seven and Twenty Nine Paise Only
19	KSRB 5-8.3 : Providing three line dressing to granite stone slab / granite stone masonry as per specifications. KBS 5.1.13	Sqm	33.66	2144.93	Rupees Two Thousand One Hundred Forty Four and Ninety Two Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,